

Case Study

PROJECT

Victoria Park Baptist Church

London

VALUE

£372,000.00

SCOPE

Stripping works:

Strip slates, underlay and timber battens.

Structural survey:

Structural survey carried out and a report supplied of required works

Following the survey and report, carry out the following works. Wire brush and paint steels with intumescent paint. Install reinforcing steel brackets to the purling ends

Installation works:

Install new breathable underlay to the roof area.

Install new fully graded (to BS5534) timber batten to the roof area.

Install new Spanish slate to the entirety of the roof, in accordance with BS5534

Bed new replacement ridge tiles in new mortar

Install Code 4 lead stepped cover flashings to abutments.

Install a new suspended ceiling.

Install 2no. layers of 150mm loft insulation to the suspended ceiling.



Case Study



Completed Works

